

BOARD OF COUNTY COMMISSIONERS
ESCAMBIA COUNTY, FLORIDA
OFFICE OF PURCHASING

213 PALAFOX PLACE, 2nd Floor
P.O. BOX 1591
PENSACOLA, FL 32591-1591
TELEPHONE (850) 595-4980
(SUNCOM) 695-4980
TELEFAX (850) 595-4805
<http://www.myescambia.com>



CLAUDIA SIMMONS
Chief, Purchasing

July 20, 2010

To: All Prospective Bidders:

ADDENDUM NUMBER 1:

Re: Audio Visual Systems Upgrades at Escambia County Public Safety
PD# 09-10.071

Bidders:

We recently sent you a Invitation to Bid on the above-mentioned specification.

This Addendum #1 provides for the following:

Please remove and replace the following pages:

Page 4 Bid Form adding:

3	Extron	60-231-01	HD15M to 5BNCF 6" Adapter	\$ _____
3	Extron	60-532-01	HD15F to 5BNCF 6" Adapter	\$ _____
As Required	Contractor	BNCM	3 Part BNCM Connectors	\$ _____

Page 11130-9 of Exhibit 1 Under Project Conditions 1.14 adding:

While there is no mandatory site inspection; Site inspections can be arranged through the Consultant, David Ebbert, Walthall & Associates at (850) 478-9002, up to 24 hours prior to receipt of bids.

This Addendum Number 1 is furnished to all known prospective bidders. Please sign and return one copy of this addendum with your original signature, with your bid, as an acknowledgement of your having received same.

Sincerely,

A handwritten signature in blue ink that reads "Joe F. Pillitary".

Joe Pillitary, CPPO, CPPB
Purchasing Coordinator

SIGNED: _____

COMPANY: _____

JP/lk

Addendum #1
PD 09-10.071

BID FORM
Specification Number PD 09-10.071
AUDIO VISUAL SYSTEMS UPGRADES AT ESCAMBIA COUNTY PUBLIC SAFETY

Board of County Commissioners
 Escambia County, Florida
 Pensacola, Florida 32502

Date: _____

Commissioners:

In accordance with your "Invitation for Bids" and "Instructions to Bidders" for **AUDIO VISUAL SYSTEMS UPGRADES AT ESCAMBIA COUNTY PUBLIC SAFETY** as described and listed in this Invitation for Bids, and subject to all conditions thereof, I, undersigned, hereby propose to provide at the following price:

TOTAL BID _____ \$ _____

Additive Alternate #1 Peaking Amplifiers

<u>QTY</u>	<u>MODEL</u>	<u>DESCRIPTION</u>	<u>UNIT PRICE</u>	<u>TOTAL PRICE</u>
9	Extron 60-319-09	VGA Line Driver	\$ _____	\$ _____
As Required Installation of Line Drivers on existing systems				\$ _____
As Required Freight to 32502 Pensacola, FL				\$ _____

Additive Alternate #2 EOC Overhead Projectors

<u>QTY</u>	<u>MODEL</u>	<u>DESCRIPTION</u>	<u>UNIT PRICE</u>	<u>TOTAL PRICE</u>
3	NEC NP4100	6.2K Lumen Single DLP 4:3 (1024X768 Projector	\$ _____	\$ _____
3	NEC NP-08ZL	1.78-2.35: 1 Zoom Lens	\$ _____	\$ _____
3	Extron 60-319-02	VGA Line Driver	\$ _____	\$ _____
3	Chief RPA-U	Universal Projector Mounting Adapter	\$ _____	\$ _____
3	Extron 60-231-01	HD15M to 5BNCF 6" Adapter	\$ _____	\$ _____
3	Extron 60-532-01	HD15F to 5BNCF 6" Adapter	\$ _____	\$ _____
<u>As Required Contractor BNCM 3 Part BNCM Connectors</u>				\$ _____
As Required Total Labor and Materials to install projectors on existing mounts				\$ _____
As Required Total Labor and Materials for miscellaneous hardware and spacers				\$ _____
As Required Total Freight to 32502, Pensacola, FL				\$ _____

Additive Alternate #3 EOC Overhead Projectors, Lens Alternate

<u>QTY</u>	<u>MODEL</u>	<u>DESCRIPTION</u>	<u>UNIT PRICE</u>	<u>TOTAL PRICE</u>
3	NEC NP-09ZL	2.22-4.43: 1 Zoom Lens	\$ _____	\$ _____
3	NEC NP-08ZL	1.78-2.35: 1 Zoom Lens	\$ _____	\$ _____
As Required Total Freight to 32502, Pensacola, FL				\$ _____

CONTRACTOR REQUIREMENTS

Acknowledgment is hereby made of receipt of the following addenda issued during the bidding period:

Addendum No. _____ Date _____ Addendum No. _____ Date _____

Addendum No. _____ Date _____ Addendum No. _____ Date _____

(PLEASE TYPE INFORMATION BELOW)

SEAL IF BID IS BY CORPORATION

State of Florida Department of State Certificate of Authority
 Document Number _____

Bidder: _____

Occupational License No. _____

By: _____

Florida DBPR Contractor's License, Certification and/or
 Registration No. _____

Signature: _____

EXHIBIT 1

Escambia Public Safety – Video Wall Upgrade

#11130 – 9

Walthall & Associates, Inc.

Video Wall Upgrade

15 June 2010

A. Operation manuals shall include, but not limited to the following sections:

- 1) Table of Contents.
- 2) Typed description of system including key features and operational concepts (e.g. remote control features, switching functions, and mixing capabilities).
- 3) Setup diagrams and typed instructions for use in typical situations as directed by the Owner.
- 4) Small scale plans showing locations and circuit numbers for all system outlets and receptacles.
- 5) Single-line block diagrams showing all major components of the systems.
- 6) Manufacturer's operation manuals for user-operated equipment (tape decks, processors, communication equipment, etc.).
- 7) Provide three bound copies with 30% additional space under this part.

1.3 MAINTENANCE MANUALS

Provide the owner any maintenance manuals that come packaged with equipment. Maintenance and users manuals shall be bound in the appropriate sized three ring binder(s), tabbed by system and arranged in alphabetical order. Provide two (2) identical copies.

1.4 PROJECT CONDITIONS

While there is no mandatory site inspection; Site inspections can be arranged through the Consultant, David Ebbert, Walthall & Associates at (850) 478-9002 up to 24 hours prior to receipt of bid.

- A. If project conditions indicate a need to vary from the Specifications or Drawings, notify the Owner and Consultant, make recommendations, and proceed with the necessary changes only after receipt of approval from the Owner and Consultant in writing.
- B. This project is new systems construction in Pensacola, FL.
- C. The AV Integrator may request a site visit. This shall be scheduled through the AV Consultant.
- D. This project will be installed in an existing building on an existing structure.
- E. The AV Integrator shall maintain a set of project drawings and all project documentation on the project site at all times. This documentation shall be updated with cable identifications, current as built configuration and noting any changes made in the field or by direction. This shall be updated daily and available for review on request.
- F. A partnering meeting will be required with the Consultant and AV Integrator prior to commencing work.
- G. Coordinate installation schedule with Owner's and AV Consultant's construction schedule.
- H. **Verify projector lensing versus distance requirements prior to ordering projector and lens. If a zoom lens is used the projector shall be mounted in the center of the zoom range. Improper lensing shall be corrected (lens replaced) at no addi**

Addendum #1